THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE PROPERTY OF FHI CORP. AND IS NOT TO BE COPIED OR DISCLOSED TO THIRD PARTIES WITHOUT THE PRIOR WRITTEN CONSENT OF FHI CORP. NOR IS IT TO BE MISSUED IN ANY WAY.

SYMBOL/LEGEND	DESCRIPTION	SYMBOL/LEGEND	DESCRIPTION
PID XXX-XX-XXX	PID CONTROLLER (ANALOG OUTPUT)	H/	COMPARISON (LARGER THAN)
PIDV XXX-XX-XXX	PID CONTROLLER (PULSE OUTPUT)	/L	COMPARISON (SMALLER THAN)
ALM XXX-XX-XXX	INDICATING ALARM 4 LEVEL SETTING: (1) HIGH HIGH (2) HIGH (3) LOW LOW (4) LOW	ABS	ABSOLUTE VALUE
MAN XXX-XX-XXX	MANUAL CONTROL STATION	+	ADDITION
SUMA XXX-XX-XXX	ANALOG INTEGRATOR (ANALOG INPUT)	-	SUBTRACTION
SUMP XXX-XX-XXX	PULSE INTEGRATOR (PULSE INPUT)	X	MULTIPLICATION
1:B A B T COS	AUTO/MANUAL SWITCH FOR PID CONTROLLER & MANUAL CONTROL STATION	÷	DIVISION
1:B A B T	INTERLOCK TRACKING FOR PID CONTROLLER & MANUAL CONTROL STATION	√	SQUARE ROOT
SW 1:b a b T Y	SWITCH SW=1, Y=b SW=0, Y=a	>	HIGH SELECTOR
AI	ANALOG SIGNAL INPUT	<	LOW SELECTOR
AO	ANALOG SIGNAL OUTPUT	H L	HIGH / LOW LIMIT
A	CONSTANT	Σ △	SUMMATION
———	CONTINUOUS LINE (FOR ANALOG SIGNAL)	F(X)	LINEARIZE CURVE
- - - - - -	DASHED LINE (FOR DIGITAL SIGNAL)	f(t)	LAG FUNCTION
V	RATE LIMITER	△	DEVIATION
PO	PULSE OUTPUT	TP	TEMP / PRESSURE COMPENSATION

SYMBOL/LEGEND	DESCRIPTION	
A, B → C	OR GATE	A B C 0 0 0 1 0 1 0 1 1 1 1 1 "1"=ON "0"=OFF
A, B → C	AND GATE	A B C 0 0 0 1 0 0 0 1 0 1 1 1 "1"=ON "0"=OFF
A → B	INVERSE (NOT) GATE	A B 0 1 1 0 "1"=ON "0"=OFF
A → TON X SEC → B	ON DELAY TIMER	A: 0 1 0 B: 0 X SEC 1 0
A → TOF X SEC → B	OFF DELAY TIMER	A: 0 1 0 B: 0 1 X SEC 0
A → TPS X SEC → B	PULSE TIMER	A: 0 1 0 1 0 1 0 B: 0 X 1 SEC 0 X 1 SEC 0
A, B → S, R → C	SET, RESET	A B C 1 0 1 0 1 0 1 1 0 0 0 NC "1"=ON "0"=OFF "NC"=NOT CHANCE

SYMBOL/LEGEND	DESCRIPTION
A, B, C → AVERAGE SELECT CIRCUIT → Y	AVERAGE CALCULATION Y= (A+B+C) / 3
PRIMARY, SECONDARY → PRI/SEC/AVG SELECT CIRCUIT → Y	PRIMARY/ SECONDARY/ AVERAGE SELECT CIRCUIT

DESIGN BASE : (100% LOAD)

MAIN STEAM FLOW	: 460 T/H
COAL FLOW	: 81 T/H
CALORIE BASE	: 4450 Kcal/Kg
TOTAL AIR FLOW	: 606 T/H
PA FLOW	: 380 T/H
SA FLOW	: 200 T/H
FA FLOW	: 26 T/H

REV.	DESCRIPTION	DATE
2	As built	2017/10/03
1	Construction	2015/06/17
0	First issue	2014/10/07
DWN. BY	C.H.Tseng	2017/10/03
CHK. BY	S.P.Sheu	2017/10/03
APPR. BY	T.T.Tsai	2017/10/03

COPY

ENGINEER

REG. NO.	:
P.T.R. NO.	:
DATE	:
PLACE	:
T.I.N.	:

SHEET CONTENT: SYMBOL LIST

FORMOSA HEAVY INDUSTRIES CORP.
100, SWEIKUAN RD., JENWU, KAOHSIUNG, TAIWAN, R.O.C.

PROJECT TITLE / LOCATION: SMC LIMAY POWER PLANT PROJECT, LIMAY, BATAAN, PHILIPPINES

OWNER / ADDRESS: SMC Consolidated Power Corporation, 40 SAN MIGUEL AVENUE, MANDALUYONG CITY, 1550 METRO MANILA, PHILIPPINES

FORMOSA PLASTIC CORPORATION
ELECTRONIC GROUP

DWG NO.	REV.	SCALE	SHT.NO.
ABC-000	1	JOB NO. D3H45	3